18	Supplying of TPST with rewireable porcelain channels in SM encloser 15/32 amps Complete as per Specifcation	Nos	3.00	1350.00	Rupees One Thousand Three Hundred Fifty Only
19	Supplying and fixing 500x500x65mm polished wood board made up not less than 15mm thick plank in front plank one end provided for olding at other end fixing the same of the valve using through bolts and nuts, Complete as per Specifcation	Nos	3.00	275.00	Rupees Two Hundred Seventy Five Only
20	Supplying and fixing LED Type panel board indicating lamp with required colour suitable for 220 v AC 50Hz 12/24 V DC Group Complete as per Specifcation	Nos	3.00	350.00	Rupees Three Hundred Fifty Only
21	Supplying and drawing each PVC insulated 650/100 V grade wire in the conduct (Open or Concealed system of wiring) 7/20 or 7/36 copper wire. Complete as per Specifcation	Nos	30.00	25.00	Rupees Twenty Five Only
22	Supplying, fixing and wiring heavy duty low voltage capacitors confirming to I 2834, 3 PHASE 400/440 Volts grade for power factor improvement of rotating machinery capacitor in KVAR - rating Nos 2 KVAR Capacity Complete as per Specifcation	Nos	3.00	350.00	Rupees Three Hundred Fifty Only
23	Supplying and fixing miniature Circuit breakers on existing MCB distribution boards using necessary fixing materials and wiring Complete as per Specifcation	Nos	3.00	1075.00	Rupees One Thousand Seventy Five Only
24	Supplying, fixing, wiring earth electrode for grounding conduits, LC cutouts and other equipments on the meter board using 40mm dia 2.90mm thick GI pipe 2.50m long buried in a pit. The pit should be filled with equal proportion of solt and charcoal 150mm alround the pipe to complete depth. the connection from the pipe to the conduct etc., is to be established through GI wire of size as per ISI specifications 7.3.3 IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 throught holes of 122mm dia Complete as per Specifcation	Nos	3.00	1500.00	Rupees One Thousand Five Hundred Only
25	Supplying and fixing class A (medium duty) GI pipe wall thickness not less than 3.25mm on pole.	Nos	30.00	220.00	Rupees Two Hundred Twenty Only
26	Supply 1.1 KV class UG cable from nearest BESCOM pole to panel board including earth work and road restoratio 4 core 16 sqmm. Complete as per Specifcation	Mtrs	45.00	150.00	Rupees One Hundred Fifty Only
27	Labour charges for laying 1.1 KV class UG cable when supplied by agencies in existing trenches GI pipe / stoneware pipe/ on pole as required, Complete as per Specifcation	Mtrs	90.00	5.00	Rupees Five Only
28	Digging of trench of 0.6m deep x 0.5m wide refilling the trench to the required level and consolidating etc., Complete as per Specifcation	Mtrs	45.00	50.00	Rupees Fifty Only